

## Q40 Fencing and Gates

### PROJECT:

To be read with Preliminaries/ General conditions.

FENCING TYPE: **PARAMESH DECO 1.2m High**

### FENCING

- Supplier/Manufacturer: Paramount Steel Fence, Florida Close, Hot Lane Industrial, Stoke on Trent, ST6 2DJ  
Contact : Mike Brookes  
Tel: 07795 437868 (Office Tel 01782 833333 Fx 01782 832222)  
E-mail: mike.brookes@steelfence.co.uk
- **PANELS:** PARAMESH DECO  
Nominal Height: 1200mm  
Width panels: 3002mm  
Mesh and wire: 4mm Vertical wires spaced at Varying patterned centres (2no at 44mm, 5no at 20mm), 6mm Horizontal wires spaced at 200mm.  
2no Reinforcing 'V' Beams are incorporated in the Width of each panel  
Panels are Flush all around  
Pre Galvanised & polyester powder coated Green RAL6005 / Black RAL9005 (other colours on request).
- **POSTS:** PARAMESH RHS POSTS  
RHS 60x60x2.0mm Intermediate & Corner Posts, 1800mm o/a length  
PARAMESH RHS Posts have threaded inserts, thus no protrusions on the rear face of the post  
Posts should have 2no Additional threaded inserts, to allow for stepping, should the site require  
Posts are Pre Galvanised and polyester powder coated Green RAL6005 / Black RAL9005 (other colours on request)  
Post centres: 3025mm nominal.
- **FIXINGS:** PARAFIX BRACKETS  
Paramesh DECO panels are to be located on the face of the post and secured using the Steel Parafix Brackets with M8 'anti tamper' bolts. These Brackets firmly clamp the end vertical wires, providing a secure fixing.  
4no Parafix Brackets/Inter ; 8no / Corner Post  
**\*Note**, an extra 2no Parafix Brackets, per post face, will be required, should stepping occur

### INSTALLATION

- Set out and erect Fencing, as shown on drawings
- Installation should be undertaken by a qualified, competent experienced Fencing Contractor (Paramount Steel Fence can supply you with a selection, please ask for details):
- Sloping Ground : Different gradients can be achieved by stepping the Fencing Panels a maximum of 110mm per bay. Slopes steeper than this can be achieved either by cutting panels and introducing additional posts (reducing the post centres), or by using extra long posts (Contractor to recommend)
- Posts to be set plumb and to necessary depth – dependant on ground conditions
- Panels that are cut on site should be made good using a 2Pk Etch Primer (P68/P2599), a 2Pk Epoxy Primer(P842/P269), followed by a Vinyl Top Coat(P461). For Coastal & Heavy Industrial humid areas (river/salt environments) etc, the number of coats should be increased)
- Holes: Excavate neatly and with vertical sides.
- All concrete should be thoroughly compacted prior to the initial set.
- Exposed concrete foundations
  - Filling: Compact until air bubbles cease to appear on the upper surface.
  - Finishing: Weathered to shed water and trowelled smooth.

### PARAMESH SWING GATES

- Standard Single and Double Leaf Swing Gates, to compliment and match the above PARAMESH DECO Fence, can be supplied by Paramount Steel Fence
- Gates can be either 90 degree or 180 degree opening, left or right hung – to suit the clients needs on site